REQUEST FOR QUOTATION (RFQ) for Construction of New Pond/Farm Pond/Renovation of Pond

DATE: 15.10.2026 **RFQ NO.- CWS/ASW/01/2026-2027**

Dear Sir / Madam:

We kindly request you to submit your quotation for Construction of New Pond/Farm Pond as detailed below of this RFQ. **Deadline of submission is 06.11.2026** When preparing your quotation, please be guided by the specification given in this RFQ.

1. **Quotations may be submitted on your letter head**

and **via**

a). Hand Delivery/Courier to the address below:

Director,

Centre For World Solidarity,

D-9, Chandra Tower,

Dimna Road Mango, Jamshedpur

Jharkhand-831012

Contact Person: Tulika Mukherjee, Mobile No.-8210739318

: Shankar kaibarta: Mobile No.9113729903

: Surabhi Poddar: Mob.7001413465

It shall remain your responsibility to ensure that your quotation will reach the address above on or before the deadline.

Quotations that are received by CWS after the deadline indicated above, for whatever reason, shall not be considered for evaluation.

2. **Work Description:**

a) New Pond Construction
Total No. Of Ponds 1. SIZE 200 x 100 x 10 , Total Earth Excavation:5112 CUM max.
Embankment Dressing,

B) Rejuvation of POND

Total No. Rejuvation of POND: 300 x 150 x 07 :01, Total Earth Excavation

:8617 CUM max.

Embankment Dressing,

All required work should be complete Before 31.03.2027

3. **List Of Villages where the construction Work to be done**

Type of Work	Beneficiary Name	Village Name
New pond	Community	Duwari
Pond Renovation	Ganesh Paswan	khothilwa

Note: Above List May be Change in some cases but total quantity of Earth excavation & no of pond will be same.

4. **Work Completion:**

a.) **Within 90 Days of P.O.** failure on this a request letter should be submitted to Director CWS with genuine justification**. Payment terms may affect if fails.**

5 Payment Terms:

1. **As per Running Bill /Invoice.**

Estimates is available at our Jamshedpur Office. interested vendor may visit or Download from Website www.cws.org.in from RFQ section.

For Technical enquiry contact Shankar kaibarta: Mobile No.9113729903

6. Guideline for submit the quotation:

a) Please quote the amount with calculating all expenses like transportation, labor cost, any unseen expenses, all equipment, including GST. No any other cost will be entertained.

b) Please Quote The Rate as follows

Sl.N	Description Of Work	Particular	Quantity	Rate (Included GST INR/CUM)
1	Rejuvenated POND pyne system	Length of WHT-300 ft, Width of WHT-150 ft, Depth of WHT 7 ft, Size of Bund BW-35 .0 ft, TW-12.0 ft, Ht-12 , Slope - 1:2 (outside) & 1:2 (inside)	8617 cum	
2	NEW POND	Length of WHT-200 ft, Width of WHT-100 ft, Depth of WHT 10 ft, Size of Bund BW-35 .0 ft, TW-12.0 ft, Ht-12 , Slope - 1:2 (outside) & 1:2 (inside)	5122 cum	
	Total			

Amount In Words:

c) Please check the work completion timeline & Payment terms written in RFQ.

d) If selected workorder/supply order/purchase order will be Provided.

e) Any dispute under Jamshedpur Jurisdiction.

CENTRE FOR WORLD SOLIDARITY SEC'BAD